Notification No. Roc. 736 *S. C.* 232—27-28, *dated* 3*rd April* 1928

Notice is hereby given that sealed tenders will be received at the office of the Agricultual Engineer, Bangalore, up to 2 P.M. on 21st April 1928, for constructing a pot culture house and making certain alterations in the outbuildings in the compound of the Agricultural Office at Bangalore. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the 10th of June 1928.

Tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

Description of work	Unit	Rate

3 Each tender must be accompanied by a deposit of Rupees 100 (one hundred only) in cash as earnest money, and be superscribed "Tender for constructing a pot culture house and making certain alterations in the out buildings in the compound of Agricultural Office, Bangalore," in default of which, tenders will be rejected.

4. The final acceptance of any tender will rest withthe Agricultural Engineer who does not bind himself to accept the highest or any tender

5. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute the usual contract bond in default of which his tender will be considered cancelled, and his earnest money will be forefeited.

6 Earnest money of rejected tenders will be returned.

7. The quotations should be noted in words as well as in figures.

1. Constructing a new pot culture house and a machine room.

Sl. No.	Description	Per	Approximate quantity
1	Earthwork excavation ...	C.yd.	28
2	Concrete in mortar	C.ft	194
3	Stone in mud	,	361
4	Brick in mud	,,	694
5	Brick in mortar	,,	70
6	Stone slabs 6" thick	S.ft.	50
7	Teakwood wrought and put up	C.ft.	63·94
8	Roofing with 1st class Mangalore tiles on teak reapers ...	Sqr.	14·5
9	Ridge tiles set in mortar and concrete pointing ...	R.ft.	43
10	Teakwood doors	S ft.	53
11	Teakwood windows	,,	48
12	Chunam plastering and white washing ...	Sqrs.	21·5
13	Eave board	R.ft.	43½
14	Flooring with cudappah slabs over 3" concrete ...	Sqrs.	3·00
15	Removing expanded metal and refitting ...	,,	2·[illegible]
16	Painting doors and windows	,,	2·52
17	Wood oiling to word work	,,	7·25
18	Iron work	Cwt.	11
19	Bolts and nuts 5" x ¾	Doz.	3
20	Roofing with glass tile	Each	100
21	Mortar bund on roof	R.ft.	70
22	Earth filling	C.yds.	23
	Making certain alterations in the out-buildings.		
1	Renewing the floor with cudapah slabs ...	Sqrs.	2·5
2	Dismantling walls	C.ft.	120
3	Stone slabs 6" thick with the exposed surfaces neatly dressed.	S.ft.	30
4	Stone slabs 4" thick rough dressed	,,	25
5	Sized stone in mortar	C.ft.	10
6	Dismantling the assay, chimney and masonry beds ...	Lump sum	
7	Size stone in mud	C.ft.	19
8	Teakwood windows glazed inside and wood pannelled outside without iron bars.	S.ft.	38
9	Removing the iron bars of existing windows ..	Lump sum	
10	Flooring with first class flooring tiles on concrete and cement pointing.	Sqrs.	2·4
11	Pointing with mortar	,,	·5
12	Plastering with mortar and white washing ...	,,	·5
13	Painting with choclate 2 coats	,,	3·2

M. G. SINGARACHAR,
Agricultural Engineer.

6 *p*